

DELAWARE STATE FIRE PREVENTION COMMISSION

Statutory Authority: 16 Delaware Code, Section 6604(1) (16 Del.C. §6604(1))

1 DE Admin. Code 705

FINAL

ORDER

705 General Fire Safety

The Delaware State Fire Prevention Commission, pursuant to 16 Del.C. §6604(1), proposed to revise:

Regulation 701 by removing the limitation that the regulations apply only to buildings modified by 50% or more following the enactment of the regulations. The revision also removes Annexes A and B and reorganizes the content into a newly created Chapter 7. Finally, the revision removes references to Appendixes that are no longer part of the regulations.

Regulation 702 by making changes to the occupancy conversion regulation, clarifying the building rehabilitation requirements, clarifying the automatic sprinkler system, and standpipe regulations to prevent a submission for review and approval of a project in such stages that would have the effect of being less than 50% of the square footage of any building. These proposed changes also make substantive additions to the regulations regarding floor level identification and fire pumps.

Regulation 703 by adding a definition for "major deficiency," clarifying that at the time of renewal, a certificate holder must maintain current NICET certification at the minimum level that was required at the time of original licensure. The proposed changes also remove reference to the Annexes and Appendixes, which are no longer part of the regulations.

Regulation 704 by deleting Regulation 4.3 in its entirety, eliminating the requirement that a member of a local fire department be present on the scene of any fireworks display from the time the fireworks are delivered until the termination of the display, and reverting to Regulation 4.2, leaving the level of fire protection to the discretion of the local fire department.

Regulation 705 to clarify that one elevator car in any building must be of sufficient size to accommodate an ambulance cot in its horizontal position, and further clarifying that elevator cars existing as of September 1, 2015 are exempt from this requirement. These changes further clarify that all gates at gated communities must be either automatic or manual, and establishes guidelines for demarcating both primary and secondary entrance doors.

Regulation 706 by removing bond requirement for electricians added to the list of installers for the hard-wired smoke detector program.

Following publication in the Delaware *Register of Regulations* on August 1, 2015 a public hearing was held on September 22, 2015. Written comment periods were held open for thirty days, and an additional fifteen days following the public hearing. At the hearing, the Board accepted as evidence and marked as the Board's Exhibit 1 documentation of publication of the notice of the public hearing in the *News Journal* and as Board Exhibit 2, documentation of publication of the notice of the public hearing in the *Delaware State News*. During the written public comment period, written public comments were received from the following, and marked as indicated:

Board Exhibit 3: An August 6, 2015 letter from Bryan J. Soukup, Esquire of the International Code Council, urging the Commission to adopt the 2015 International Fire Code in its entirety and an August 28, 2015 letter from Kevin Brinkman, PE of the National Elevator Industry, Inc, requesting the Commission (1) look again at the proposed language of Regulation 15.2 as it appears to require two elevator cars that accommodate a stretcher where elevators are located on both sides of an elevator lobby, even if they served the same floors; (2) clarify what is meant by "key for access" as used in Regulation 15.3; (3) define one and two family elevators in Exception 1; (4) clarify Exception 2; (5) look again at Exception 3 and consider making a language change for consistency.

Board Exhibit 4: Technical, non-substantive changes suggested by the Office of the Fire Marshall upon further review of the proposed regulations.

Board Exhibit 5: A September 8, 2015 letter from Robert J. Duke, of the Surety and Fidelity Association of America, urging the Commission not to remove the bond requirement from the regulations.

Board Exhibit 6: An email from John Caufield, NFPA Mid-Atlantic Regional Director, indicating that the proposed regulations state that the Commission is adopting the 2002 edition of the NFPA 42: *Storage of Pyroxylin Plastic*, but the Commission had previously adopted the 2009 edition.

At the time of the public hearing, the Commission received public comment from Jeffrey Sargent of the Regional Electrical Code. Mr. Sargent indicated he was speaking in support of the regulation changes with a friendly suggestion regarding proposed Regulation 210.12 regarding circuit interrupters. Mr. Sargent indicated that residential smoke alarms are required to have dedicated branch circuits without arc pull circuit interrupters. These have been around since 1999 and they have proven to be a good fire prevention tool. Mr. Sargent asked that the Commission please do away with the ban on AFCI for smoke alarms.

The Commission also received public comment from Maria Evans with the Delaware Association of Realtors. Ms.

Evans asked what the timing of these regulation changes would be.

Summary of the Findings of Fact

Pursuant to discussions held during open public Commission meetings, it was determined that Regulation 701 needed to be revised to remove the limitation that the regulations apply only to buildings modified by 50% or more following the enactment of the regulations. The revision also removes Annexes A and B and reorganizes the content into a newly created Chapter 7. Finally, the revision removes references to Appendixes that are no longer part of the regulations. These changes are necessary to begin to revise the entire administrative code to a more clear, user-friendly regulatory structure that reflects best practices and removes out of date material.

Pursuant to discussions held during open public meetings of the Commission, it has been determined that Regulation 702 need to be changed *vis a vis* the occupancy conversion regulation, clarifying the building rehabilitation requirements, clarifying the automatic sprinkler system, and standpipe regulations to prevent a submission for review and approval of a project in such stages that would have the effect of being less than 50% of the square footage of any building. These changes also make substantive additions to the regulations regarding floor level identification and fire pumps. These changes are necessary to begin to revise the entire administrative code to a more clear, user-friendly regulatory structure that reflects best practices and removes out of date material.

Pursuant to discussions held during open public meetings of the Commission, it has been determined that Regulation 703 required the addition of a definition for "major deficiency," clarifying that at the time of renewal, a certificate holder must maintain current NICET certification at the minimum level that was required at the time of original licensure. These changes also removed reference to the Annexes and Appendixes which are no longer part of the regulations. These changes are necessary to begin to revise the entire administrative code to a more clear, user-friendly regulatory structure that reflects best practices and removes out of date material.

Pursuant to discussions held during open public hearings of the Commission, it was determined that Regulation 704 required the deletion of Regulation 4.3 in its entirety, eliminating the requirement that a member of a local fire department be present on the scene of any fireworks display from the time the fireworks are delivered until the termination of the display, and reverting to Regulation 4.2, leaving the level of fire protection to the discretion of the local fire department. These changes are necessary to begin to revise the entire administrative code to a more clear, user-friendly regulatory structure that reflects best practices and removes out of date material.

Pursuant to discussions held during open public hearings of the Commission, it was determined that Regulation 705 needed to be clarified to indicate that one elevator car in any building must be of sufficient size to accommodate an ambulance cot in its horizontal position, and further clarifying that elevator cars existing as of September 1, 2015 are exempt from this requirement. These changes were further needed to clarify that all gates at gated communities must be either automatic or manual, and establish guidelines for demarcating both primary and secondary entrance doors. These changes are necessary to begin to revise the entire administrative code to a more clear, user-friendly regulatory structure that reflects best practices and removes out of date material.

Pursuant to discussions held during open public hearings of the Commission, it was determined that Regulation 706 required removal of the bond requirement for electricians added to the list of installers for the hard-wired smoke detector program. These changes are necessary to begin to revise the entire administrative code to a more clear, user-friendly regulatory structure that reflects best practices and removes out of date material.

Decision of the Board

With regard to the letter from Bryan J. Soukup, Esquire of the International Code Council, urging the Commission to adopt the 2015 International Fire Code in its entirety, the Commission finds that Delaware is a NFPA state, we have always have followed the NFPA and not the International Codes for the Fire Codes. Although municipalities may adopt the IFC, that is generally more stringent than the NFPA, which municipalities are free to therefore adopt. However, the NFPA is the state fire standard that has always been used and changing to the International code.

With regard to the letter from Kevin Brinkman, PE of the National Elevator Industry, Inc, regarding Regulation 15.2, when the committee met to discuss this change, the committee felt that if one elevator in a hoistway is placed out of service for maintenance, there would still be an stretcher accommodating elevator available in another hoistway. Currently, every elevator must be stretcher accommodating, so this is a less onerous requirement than the current regulation. "Keys to access" refers to the fire fighter recall key. The Commission will change "Keys for access" to "fire fighter recall key" as suggested. Further, one and two family dwellings are defined elsewhere in the regulations and, moreover, are outside of the jurisdiction of this Commission. The term "dwelling" will be added after the term "one and two family" as suggested. Exception 2 eliminates the requirement for an elevator that accommodate a stretcher if the outside grade permits stretchers to access upper levels from the outside. This is clear. Exception 3, however, will be rewritten as suggested.

The technical, non-substantive changes suggested by the Office of the Fire Marshall will be made.

With regard to the letter from Robert J. Duke, of the Surety and Fidelity Association of America, urging the Commission not to remove the bond requirement from the regulations, the Commission finds that the bond requirement was originally

added due to the bid requirements. Ultimately, the amount of the bond that was being required was in excess of the projects under bid. Changes in state law and procurement procedures have rendered the bond requirement superfluous.

With regard to the email from John Caufield, NFPA Mid-Atlantic Regional Director, indicating that the proposed regulations state that the Commission is adopting the 2002 edition of the NFPA 42, this is a typographical error and will be corrected.

With regard to the public comment from Jeffrey Sargent of the Regional Electrical Code regarding circuit interrupters, the Commission finds the ban is necessary because a circuit may trip and a homeowner would not even know it. When originally put in, there was a great deal of contention as to whether the AFCI would work as contemplated. Now, the ban has been in place for so long and it's working so the Commission is not inclined to remove the ban.

Therefore, the Commission adopts the regulations as proposed, with the minor non-substantive changes reflected in Exhibit A.

IT IS SO ORDERED this 17th day of November, 2015 by the Delaware State Fire Commission.

David J. Roberts, Chairman
Anthony Guzzo
Marvin C. Sharp (absent)
Tom DiCristofaro

Alan Robinson, Jr., Vice Chairman
Ron Marvel
Lynn Truitt

705 General Fire Safety

Chapter 1 General Fire Safety Requirements

1.0 General Precautions.

1.1 Ordinary Conduct Requirements.

- 1.1.1 Spread of Fire.** No person shall knowingly permit any fire to spread so as to endanger life or property of another or use or operate any device which may be a source of ignition unless proper removal of flammable material surrounding the operation is accomplished or such other reasonable precautions are taken to ensure against the starting and spreading of unfriendly fires.
- 1.1.2 Burning of Construction Materials.** During construction or demolition of buildings or structures no waste materials or rubbish shall be disposed of by burning on the premises or in the immediate vicinity.

Exception: Small amounts of construction materials may be burned for the purpose of providing warmth for construction workers provided such materials are burned in an approved container located at least 30 feet from any structure or combustibles and provided the fire is constantly attended by a competent person until such fire is extinguished.

- 1.1.3 Bonfires and Rubbish Fires.** No person shall kindle or maintain any bonfire or rubbish fire or authorize any such fire to be kindled or maintained on any private land unless:
 - 1.1.3.1** The location is not less than fifty feet (50') from any structure and adequate provision is made to prevent fire from spreading to within fifty feet (50') of any structure; or
 - 1.1.3.2** The fire is contained in an approved waste burner located safely not less than thirty feet (30') from any structure. Bonfires and rubbish fires shall be constantly attended by a competent person until such fire is extinguished. This person shall have a garden hose connected to the water supply or other fire extinguishing equipment readily available for use.
- 1.1.4 Other Outdoor Fires.** No person shall kindle or maintain any controlled burning, agricultural burning, fires for land clearing, or fires for demolition and removal of hazards without first notifying the local fire dispatch center of the time and date of the burning.
- 1.1.5 Authority to Prohibit All Outdoor Fires.** The State Fire Marshal may prohibit any and all bonfires, controlled burnings, agriculture burnings, land clearing, fires for demolition and removal of hazards, and out-door rubbish fires whether or not contained, when atmospheric conditions or local circumstances make such fires hazardous. During such time the State Fire Marshal may issue a special burning permit to those persons who show just cause and provide adequate safeguards to prevent the fire from spreading.
- 1.1.6 Notifying the Fire Department.** Whenever an unfriendly fire occurs in any building or on any premises of any kind, the owner, manager, occupant, or any person in control of such building or premises, upon discovery of an unfriendly fire, or evidence of there having been an unfriendly fire, even though it has

apparently been extinguished, immediately shall cause notice of the existence of such fire, circumstances of same, and the location therefore to be given to the fire department. This requirement shall not be construed to forbid the owner, manager, or other person in control of the aforementioned building or premises from using all diligence necessary to extinguish such fire prior to the arrival of the fire department. No person shall make, issue, post, or maintain any regulation or order, written or verbal, that would require any person to take any unnecessary delaying action prior to reporting a fire to the fire department.

- 1.1.7 **Reporting Hazardous Condition.** Any person, upon discovering evidence of spontaneous heating or other abnormal heating of any merchandise, commodity, cargo, shipment, or other material of any kind in any building, marine vessel, appliance, apparatus, tank, or open stack pile, or any person upon discovering or being apprised of any uncontrolled hazardous gas leak or hazardous material or combustible or flammable liquid spill, shall immediately notify the fire department.
- 1.1.8 **Reporting of Fire Incidents.** Any fire brigade, department, or company shall report all incidents to the State Fire Marshal in an electronic format acceptable to the State Fire Marshal within ten days after the end of the month in which the incident occurs.
- 1.1.9 **False Alarm.** No person shall deliberately or maliciously turn in an alarm of fire when in fact that person knows that no fire exists. No person shall activate an installed fire warning or extinguishing system for purposes other than emergency, maintenance, drills, or prescribed testing.
- 1.1.10 **Evacuation of Building.** Whenever an unfriendly fire occurs in any building, premises, or fire area of any kind, or upon the initiation of a fire alarm all occupants shall evacuate the building, premises, or fire area immediately and shall not re-enter the building, premises, or fire area unless permission is given by the Fire Chief or Fire Officer in charge of the scene.

Exception: Occupancies, where by the nature of the occupants it is impractical to immediately evacuate the occupants.

- 1.1.11 **Maintaining a Fire Hazard.** No person shall knowingly maintain a fire hazard.
- 1.1.12 **Carelessness With Fire.** No person shall deliberately, or through carelessness or negligence, set fire to or cause the burning of any bedding, furniture, rug, curtain, drape, or other combustible material, in such manner as to endanger the safety of any person or property.
- 1.1.13 **Posting of Fire Exit Plans.** Residential occupancies designed for, intended for, or used by transients shall have an approved copy of fire exit plans conspicuously posted in the lobby and each occupancy unit and at such other locations as may be required by the State Fire Marshal.
- 1.1.14 **Notification of Fire Department of Inoperative Fire Safety Equipment.** Persons owning, controlling, or otherwise having charge of any fixed fire extinguishing or fire warning system or standpipe system shall notify the fire department and Office of the State Fire Marshal at any time such system or systems are inoperable or taken out of service. Both shall also be notified when service is restored.
- 1.1.15 **Barricading Vacant Buildings.** Every person owning or having charge or control of any vacant building shall remove all combustible waste and refuse therefrom and lock, barricade, or otherwise secure all windows, doors, and other openings in the building to prohibit entry by unauthorized persons.

Exception: This section is not intended to apply to the temporary vacating of a building for tenant change or remodeling purposes. Temporary in this case shall mean a period of time not to exceed forty-five (45) days.

- 1.1.16 **Smoking.** Where in the opinion of the State Fire Marshal conditions exist which make smoking a fire hazard on any premises, "No Smoking" signs shall be posted as directed by the State Fire Marshal. "No Smoking" signs shall be of a color, size, lettering, and location as approved by the State Fire Marshal. No person shall remove such "No Smoking" signs or light, ignite, or otherwise set fire to or smoke any cigar, cigarette, pipe, tobacco, or other form of smoldering substance nor hold, possess, throw, or deposit any lighted or smoldering substance in any place where it would constitute a fire or life hazard.
 - 1.1.16.1 Nothing in the foregoing provision shall be construed as prohibiting smoking in areas, offices, or other rooms which have been designated by the State Fire Marshal as safe smoking areas and have been approved for such purpose.
- 1.1.17 **Use of Torches, Welders, or Laser Cutting Devices.** Any person using a torch or other flame producing device, welder, or laser cutting device in any building or structure shall provide one (1) approved fire extinguisher or water hose connected to the water supply on the premises where such burning is done. In all cases, the person doing the burning shall remain on the premises one (1) hour after the torch or flame producing device has been used.

- 1.1.18 **Hazardous Gas in Balloons.** No person shall use any flammable, oxidizing, toxic, corrosive, or reactive gas to inflate balloons. Air and inert gases, such as helium and nitrogen, are not prohibited for this purpose.

Exception: This section shall not prohibit filling of laboratory balloons with samples of test gases.

- 1.1.19 **Fire Doors.** Fire doors shall be kept closed at all times.

Exception: This section shall not apply to doors held open with automatic releasing hold-open devices installed and maintained in accordance with the applicable provisions of the Standard for Fire Doors and Fire Windows, NFPA 80, and the Life Safety Code, NFPA 101, as adopted and/or modified by these Regulations.

- 1.1.20 **Interference With Fire Protection Equipment.** No person shall render any portable or fixed fire extinguishing system or device or any fire warning system inoperative or inaccessible, except as may be necessary during emergencies, maintenance, drills or prescribed testing.

2.0 Reserved

13 DE Reg. 629 (11/01/09)

16 DE Reg. 620 (12/01/12)

3.0 Fire Drills in Educational and Institutional Occupancies.

- 3.1 Fire drills shall be held at least once a month in educational occupancies where such occupancies constitute the major occupancy of a building and at least once every two months in institutional occupancies where such occupancies constitute the major occupancy of a building. During severe weather, fire drills may be postponed. A record of all fire drills shall be kept and persons in charge of such occupancies shall maintain a written record on site of all such fire drills held, giving the time and date of each drill held. This record of fire drills shall be made available to a representative of the State Fire Marshal, upon request. The record shall be maintained for a period of three years, not including the current year.

Note: Change relieves facilities from requirement of sending reports to the State Fire Marshal.

- 3.2 In educational occupancies fire drills shall include complete evacuation of all persons from the building. In institutional occupancies fire drills shall be conducted to familiarize operating personnel with their assigned positions of emergency duty; complete evacuation of all persons from the building at the time of the fire drill shall be required only where it is practicable and does not involve moving or disturbing persons under medical care.

4.0 Precautions Inside Buildings.

- 4.1 **Sweeping Compounds.** Only approved water solutions or detergents, floor sweeping compounds, and grease absorbents shall be used for cleaning floors. The use of sawdust or similar combustible materials to soak up combustible or flammable liquids spilled or dropped from machinery or processes on any floor is prohibited.
- 4.2 **Lighting and Heat Producing Equipment.** Proper clearances shall be maintained between heating and lighting equipment and ordinary combustibles in accordance with these Regulations. In the absence of a specific regulation, the State Fire Marshal shall designate proper clearances based on sound engineering judgment. Lighting and heating processes and equipment utilizing flammable or combustible liquids shall be designed in accordance with these Regulations.
- 4.3 **General Use of Combustible And Flammable Materials.** Flammable or combustible materials shall not be used for decorative or display purposes in any part of a building occupied by the public in such a quantity or manner so as to constitute a fire hazard unless such material is flame-proofed or fire retardant treated in a manner acceptable to the State Fire Marshal.
- 4.4 **Disposal of Combustible Waste.**
- 4.4.1 Combustible waste or refuse shall be properly stored or disposed of at the end of each working day, before vacating a building or premises, and whenever necessary to prevent creating a fire hazard. The term "properly stored or disposed of" shall mean removed from the building or to within a room or area specifically designed and approved for such storage.
- 4.4.2 Rubbish within Dumpsters

- 4.4.2.1 Dumpsters and containers with an individual capacity of 1½ cubic yards or more shall not be stored in buildings; or placed within 10 feet of combustible walls, openings, or combustible roof eave lines.

Exception 1: If areas containing dumpsters or containers are protected by an approved automatic sprinkler system and enclosed with a fire resistance rating of 1 hour.

- 4.4.2.2 Structures of Types I and Type II construction (as defined in NFPA 220) used for dumpster or container storage shall be located not less than 10 ft from openings and other buildings.

5.0 Waste Disposal Sites.

- 5.1 **Fire Extinguishing Capabilities.** Fire extinguishing capabilities approved by the State Fire Marshal shall be provided at waste disposal sites including, but not limited to, fire extinguishers, water supply and hose, and earth moving equipment.
- 5.2 **Dumping of Burning Load Prohibited.** Burning debris shall not be dumped at a waste disposal site except at a remote location on the site where fire extinguishment can be accomplished before compacting, covering, or other disposal activity is carried out.
- 5.3 **Transportation of Combustible Waste and Refuse.** Vehicles or conveyances used to transport combustible waste or refuse over public thoroughfares shall have all cargo space covered and maintained sufficiently tight to ensure against ignition from external fire sources and scattering burning and combustible debris which may come in contact with ignition sources. Transporting burning waste or refuse is prohibited.
- 5.4 **Waste Handling Plants.** All structures housing operations which are involved primarily in the handling, storage, or baling of combustible waste materials shall be equipped with an automatic fire extinguishing system installed in accordance with these Regulations.

6.0 Factors Affecting Egress.

- 6.1 **General Requirements.**
 - 6.1.1 **Means of Egress.** Means of egress shall be provided and maintained in accordance with the applicable provisions of these Regulations.
- 6.2 **Storage on Roofs and Fire Escape Balconies.** No person shall place or maintain upon any roof or fire escape balcony any materials or objects which may interfere with egress or fire department operations.
- 6.3 **Attachments to Fire Escapes and Fire Protection Equipment.** No person shall attach or fasten any rope, wire, cable, or similar device, to any part of any fire escape, standpipe, auxiliary fire fighting equipment, appliance, or other apparatus.
- 6.4 **Responsibility to Prevent Overcrowding.** The manager or person in charge of the premises shall be responsible for preventing overcrowding as specified by the State Fire Marshal. At no time shall the posted occupant load, as established by the Office of the State Fire Marshal, be exceeded within any building or premise.
- 6.5 **Obstruction of Aisles and Passageways.** No person shall block, impede, or obstruct any aisle, passageway, hallway, lobby, foyer, or stairway leading to or from any entrance or exit required by law which will prevent, delay, hinder, or interfere with the free use of such passageway by any person. Special security or security devices which affect the exiting shall be subject to the approval of the State Fire Marshal.
- 6.6 **Failure to Vacate.** No person shall fail to leave any premises which are overcrowded when told to do so by the management of the premises or any authorized enforcement officer.

7.0 Treatment of Interior Finishes and Furnishings.

- 7.1 **Fire Retardants.** The provisions of 7.2 and 7.3 of this Chapter shall be applicable to all chemical formulations, paints, coatings, or other finishes which are sold, offered for sale, or advertised, and which purport to reduce the surface flamespread rating or to reduce or eliminate combustible characteristics of furnishings and structures.
- 7.2 **Approval and Tests.** No person shall sell, or offer for sale, any chemical formulation, paint, coating, or other finish which purports to reduce flame-spread rating or to reduce or eliminate combustible characteristics of furnishings or structures that have not been approved by the State Fire Marshal.

Note: Listing by a nationally recognized testing agency or laboratory accepted by the State Fire Marshal constitutes, in this case, State Fire Marshal approval.
--

- 7.3 **Applicators of Fire Retardant Coatings.** Every applicator of fire retardant coating shall certify to the State Fire Marshal that applications of such coatings comply with the manufacturer's specifications.

8.0 Combustible Decorations.

- 8.1 **General Use of Combustible Decorations.** No person shall install, maintain, or use vegetation, bunting, cotton batting, plastic cloth, textile, excelsior, paper, or other combustible material for the purpose of decoration in any building, premises, vehicle, or marine vessel to which the public is admitted or invited unless such decorative materials have been made flame resistant with an approved flame retardant material or process in accordance with applicable NFPA Codes and Standards adopted and/or modified by these Regulations.

Exception: This paragraph shall not apply to materials used in display or other material which is limited in quantity and approved by the State Fire Marshal for such use.

- 8.2 **Fire Tests.** Tests for determining flammability of combustible decorations shall be conducted in accordance with applicable tests for the type of combustible decoration involved.
- 8.3 **Interior Finishes.** Textiles, paper, or other combustible materials adhered to walls and ceilings, (not free hanging) must comply with the interior finish requirements of the applicable codes and standards listed in Regulation 701[~~Annex A~~].
- 8.4 **Christmas Trees.**
- 8.4.1 Natural cut Christmas trees, including living trees in a balled condition with their roots protected by an earth ball, shall not be permitted in Assembly, Educational, Health Care, Residential Board and Care, Detention and Correctional, Mercantile, Hotel, or Dormitory occupancies.

Exception No. 1: Trees located in areas protected by an approved automatic sprinkler system.

- 8.4.2 Artificial Christmas trees shall be labeled or otherwise identified or certified by the manufacturer as being "flame retardant" or "flame resistive."
- 8.4.3 No Christmas trees shall be allowed to obstruct exits in any way or be located in corridors, exit ways, or other means of egress.
- 8.4.4 Only listed electrical lights and wiring shall be used on Christmas trees and similar decorations.
- 8.4.5 Electrical lights are prohibited on metal artificial trees.
- 8.4.6 Open flames such as from candles, lanterns, kerosene heaters, and gas fired heaters shall not be located on or near Christmas trees or other similar combustible materials.
- 8.4.7 Natural cut Christmas trees shall not be located near heating vents or other fixed or portable heating devices that could cause the tree to dry out prematurely or to be ignited.
- 8.4.8 In occupancies where natural trees are permitted, the bottom end of the trunk shall be cut-off at an angle at least one to two inches (1-2") above the end to help the tree absorb water. The tree shall be placed in a suitable stand with adequate water. The water level shall be checked and maintained on a daily basis. The tree shall be removed from the building immediately upon evidence of dryness.

9.0 Fire Protection Required.

- 9.1 **Portable Fire Extinguishers.** Portable fire extinguishers shall be installed in all buildings in accordance with the provisions of the Standard for Portable Fire Extinguishers, NFPA 10, as adopted and/or modified by these Regulations.

Exception: One- and two-family dwellings are exempted from this requirement.

- 9.2 **Automatic Fire Extinguishing Systems, Automatic Sprinkler Systems and Standpipes.** Automatic fire extinguishing systems, automatic sprinkler systems, and standpipes shall be required as set forth in these Regulations.
- 9.3 **Maintenance of Equipment.** All systems, equipment, tanks, piping, devices, appliances, controls, or storage facilities, over which these Regulations contain regulatory provisions, shall be maintained in operative condition at all times to provide the service for which installed.

- 9.4 **Water Supply and Fire Hydrants.** The State Fire Marshal may require that all premises, other than one- and two-family dwellings, be provided with a water supply system installed in accordance with these Regulations.

10.0 Flammable and Combustible Liquids.

- 10.1 Flammable and combustible liquids shall be stored, handled, and used in accordance with the applicable provisions of the codes and standards as adopted and/or modified by these Regulations.
- 10.2 Transportation of flammable and combustible liquids shall comply with the provisions of The Hazardous Materials Transportation Act as provided in 29 **Del.C.**, §8223 through §8230.

11.0 Compressed And Liquefied Gases.

- 11.1 Compressed and liquefied gases shall be stored, handled, transported, and used in accordance with the applicable provisions of the codes and standards as adopted and/or modified by these Regulations.
- 11.2 Storage and handling of compressed and liquefied gases not covered by the above referenced codes and standards shall comply with applicable provisions of:
- 11.2.1 Standards of the American National Standards Institute (ANSI);
 - 11.2.2 Code of Federal Regulations, Title 49, Parts 173 through 190 (transportation);
 - 11.2.3 Pressure Vessels, section VIII of the American Society of Mechanical Engineers Boiler and Pressure Vessel Code (container fabrication); or
 - 11.2.4 The container fabrication specifications of the American Petroleum Institute.

12.0 Dusts.

12.1 Applicability.

- 12.1.1 This section shall be applicable only to those operations or occupancies involving combustible dusts which are not otherwise regulated by an applicable NFPA code or standard as adopted and/or modified by these Regulations.

12.2 General Requirements.

- 12.2.1 The accumulation of dust in quantities sufficient to create a fire or explosion hazard on electric motors, walls, ledges, or other interior surfaces, or on the roof of any building on which dust may settle is prohibited. Metallic dust shall be stored in tightly covered metal containers in a cool, dry place.
- 12.2.2 Every plant, factory, workshop, or other premises in which dust is produced as a product or as a result of operations in the production of other products in such quantities as to create a possible fire or explosion hazard, shall be equipped and maintained with an approved pneumatic or mechanical dust collection system designed, maintained, and operated in accordance with applicable NFPA codes and standards as adopted and/or modified by these Regulations.

Exception: This section shall not apply to storage bins equipped with explosion vents of sufficient area to relieve any explosion to the outside atmosphere.

- 12.2.3 All dust-producing or dust-agitation machinery, such as grinding mills and separators, and all elevators, elevator legs, spouts, hoppers, and other conveyors shall be provided with casings or enclosures maintained as nearly dust-tight as possible.
- 12.2.4 Approved magnetic or pneumatic separators shall be installed ahead of all shellers, crackers, crushers, grinding machines, pulverizers, and similar machines in which the entrance of foreign materials may cause sparks to be generated.
- 12.2.5 All machinery and metal parts of the crushing, drying, pulverizing, and conveying systems shall be electrically grounded.

12.3 Explosion Prevention and Suppression.

- 12.3.1 Dust explosion hazards shall be minimized by use of appropriate control measures as set forth in the applicable NFPA codes and standards as adopted and/or modified by these Regulations. The Standard on Explosion Prevention Systems, NFPA 69, and Guide for Venting of Deflagrations, NFPA 68, may be used to meet the requirements of this paragraph with due regard to the precautionary measures contained in these publications.

12.4 Sources of Ignition.

- 12.4.1 **Smoking and Open Flames.** Smoking and the carrying of matches, the use of heating, or other devices employing an open flame, or the use of any spark-producing equipment is prohibited in areas containing

dust-producing, and/or dust-agitation operations.

- 12.4.2 **Electrical Power and Lighting.** Artificial lighting in areas containing dust-producing or dust-agitation operations shall be by electricity. All electrical wiring and equipment in such areas shall be installed in accordance with the provisions of the National Electrical Code, NFPA 70, for Class II Hazardous Locations. The State Fire Marshal shall be responsible for designating the areas requiring hazardous location electrical classification and shall classify the area in accordance with the classification system set forth in the National Electrical Code, NFPA 70, as adopted and/or modified by these Regulations.
- 12.4.3 **Portable Fire Extinguishers Required.** Portable fire extinguishers shall be installed for extra hazard occupancy protection.

13.0 Hazardous Materials.

- 13.1 **Applicability.** This section shall apply to hazardous materials not covered under the NFPA codes and standards adopted and/or modified by these Regulations.

13.2 Matches.

- 13.2.1 **Type Permitted.** Matches permitted under this Regulation shall be capable of withstanding a temperature of 200 degrees Fahrenheit for eight (8) consecutive hours without igniting in a standard laboratory test.
- 13.2.2 **Packaging and Labeling.** Matches shall be labeled and packed in conformance with U.S. Department of Transportation specifications.
- 13.2.3 **Storage Requirements.** Matches in excess of 50 pounds, including the containers, shall not be stored within ten feet (10') of any open elevator shaft, elevator shaft opening, open stairway, or other vertical opening.
- 13.2.4 **Sources of Ignition.** Matches shall not be within ten feet (10') of any boiler, furnace, stove, open flame, or similar source of ignition.
- 13.2.5 **Storage at Wholesale Outlets.** For storage at wholesale establishments and other locations where containers of matches are stored in piles exceeding 100 cubic feet, such containers shall be arranged so as not to exceed ten feet (10') in height nor 1500 cubic feet in volume with aisles at least eight feet (8') wide.
- 13.2.6 **Match Storage With Other Commodities.** When case lots of matches are stored in the same room with other materials or commodities, they shall be separated therefrom by a clear space of not less than eight feet (8').

13.3 Storage of Hazardous Materials.

- 13.3.1 Hazardous materials which, when mixed, react violently or evolve toxic vapors or gases or which, in combination, become hazardous by reason of toxicity, oxidizing power, flammability, or other properties shall be separated from each other in storage by distance, partitions or other approved manner so as to preclude accidental contact between them.

13.4 Warning Signs.

- 13.4.1 The State Fire Marshal may require warning signs wherever hazardous materials are stored or processed or handled. Such warning signs shall be conspicuously lettered in accordance with the Standard System for the Identification of the Fire Hazards of Materials for Emergency Response, NFPA 704, as adopted and/or modified by these Regulations.

Exception: This section shall not apply to hazardous materials when in transport which are placarded in accordance with Department of Transportation regulations, or applicable provisions of other NFPA codes and standards adopted and/or modified by these Regulations.

13.5 Transportation of Hazardous Materials.

- 13.5.1 Transportation of hazardous materials shall comply with the provisions of The Hazardous Materials Transportation Act as provided in 29 Del.C., §8223 through §8230.

14.0 Covered Malls and Class "A" Places of Assembly.

Note: This section provides two options for occupancies where exhibits, displays, craft shows, trade shows, etc., can obtain permits for individual events.

(1) Obtain an annual license to do so and file an application for a permit for each event where the floor plan or specifications may not be able to be defined or shown to be permanent. This provision calls for a thirty (30) day notice to the State Fire Marshal and a floor plan or specification for each event.

(2) Obtain an annual license to do so and provide a floor plan or specification seeking an approval from the State Fire Marshal for such area used for all events to be held during the annual license period. This provision allows a five (5) day notice prior to the scheduled opening of an event to the State Fire Marshal.

- 14.1 All covered malls and Class "A" places of assembly where exhibits, displays, craft shows, trade shows, etc., that are of a temporary duration, shall obtain an annual license from the State Fire Marshal, to conduct or hold such operations.
- 14.2 Any covered mall and Class "A" places of assembly required under §14.1 of this Chapter to have an annual license to engage in such operations, shall obtain from the State Fire Marshal, a permit for each such exhibit, display, craft show, trade show, etc., that is held.
- 14.3 Such licenses and permits required in this section will be on forms provided by the State Fire Marshal.
 - 14.3.1 The license year period shall expire on a date as scheduled by the State Fire Marshal, pursuant to the provisions of 16 **Del.C.** §6612(g)(5)(d).
 - 14.3.2 Permits will be valid for the dates indicated and will coincide with the scheduled dates of the exhibit, display, craft show, trade show, etc.
- 14.4 In order to secure a permit as required in §14.3 of this Chapter, the owner of such covered mall and Class "A" places of assembly shall submit an application for such permit to the State Fire Marshal, at least 30 days prior to the scheduled opening of the event.
 - 14.4.1 Accompanying the application for permit as described in this section, the owner will submit a floor plan detailing the location or positioning of all displays, exhibits, etc., detailing the number and width of all aiseways, required means of egress, and exits.
- 14.5 The State Fire Marshal will inspect the location of the covered mall and Class "A" places of assembly to ensure that the arrangement of all such displays, exhibits, etc., are in compliance with the floor plan as submitted with the application for the permit.
- 14.6 The owner of the covered mall and Class "A" places of assembly is responsible to ensure that all provisions of the State Fire Prevention Regulations are complied with during such times as the display, exhibit, etc., are open to the attendees.
- 14.7 Any violations of the State Fire Prevention Regulations with respect to this section shall be remedied and/or action taken by the State Fire Marshal as provided for in the State Fire Prevention Regulations or found in 16 **Del.C.**, Chapter 66.
- 14.8 In the administration of this section, the State Fire Marshal, for those occupancies who have obtained an annual license under this Chapter may:
 - 14.8.1 Accept a floor plan or specifications from the applicant, that will detail an area or section of the occupancy that may be designated by the State Fire Marshal to be utilized for the exhibits, displays, craft shows, trade shows, etc., such approval to be in effect for the period for which the annual license is issued. Such designated floor plans or specifications will relieve the applicant from submitting an individual floor plan or specification for each individual exhibit, display, craft show, trade show, etc., as long as only the approved, designated area or space is utilized.
 - 14.8.2 Such floor plans or specifications in §14.8.1 shall detail the location and identification of all means of egress, exits, and such areas to be maintained clear under the provisions of the State Fire Prevention Regulations.
- 14.9 For those occupancies, who comply with the provisions of §14.8 of this Chapter, the application for the permit for each individual exhibit, display, craft show, trade show, etc., is to be submitted to the State Fire Marshal no later than five (5) days prior to the scheduled opening of the event.

15.0 Elevators.

- 15.1 All new passenger elevators in a building shall be provided with a ~~cab~~ car sized to accommodate an ambulance cot 24 inches (609 mm) by 76 84 inches (2133 mm) in its horizontal open position.
- 15.2 Where two or more new passenger elevators are located in a single hoist way and serve all or the same portion of the building, only one elevator car that provides a car sized to accommodate an ambulance cot 24 inches by 84 inches in its horizontal position for each hoist way shall be required.
- 15.3 Elevator cars required to comply with 15.1 or 15.2 shall be identified by the international symbol for emergency medical services (star of life). The symbol shall be not less than 3 inches (76 mm) in height and shall be placed inside on both sides of the hoist way door frame. ~~[Key for access Firefighter recall keys]~~ shall be provided in a manner acceptable to the local fire department.

Note: The words "to accommodate" in this context is intended to mean the cot is in the horizontal position and shall travel in to the elevator without having to modify the position. Additionally once the cot is in place in the ~~cab~~ car, there should be room for at least two (2) EMS attendants.

*Exception No 1: Construction, Freight, and One- and Two-Family **[Dwelling]** Elevators are not required to comply with this section.*

Exception No 2: Where all occupiable areas of all stories of the building have access to the outside at grade and the grade is accessible to fire department personnel, elevators are not required to comply with this section.

*Exception No 3: Elevator cars existing as of September 1, 2015 shall not be required to meet the requirements of **[15.0 this section.]***

- 15.24 For elevators in high rise buildings, the requirements of Regulation 702, ~~Chapter 5, §2-6~~ shall also apply.

Chapter 2 Electrical Inspection Required

1.0 General.

- 1.1 This Chapter shall apply to all occupancies including one- and two-family dwellings.
- 1.2 All electrical conductors and equipment installed after the adoption of these Regulations shall conform to the applicable NFPA codes and standards as adopted and/or modified by these Regulations.
- 1.3 All electrical conductors and wiring shall be inspected and approved by an electrical inspection agency approved by the State Board of Electrical Examiners and recognized by the State Fire Marshal, prior to occupancy.
- 1.4 For the purpose of electrical inspections under this Chapter electrical conductors and equipment includes those portions of fire protection systems that incorporate electrical current carrying wiring and devices.

2.0 Electrical Inspection for Specific Occupancies.

- 2.1 A letter of approval of electrical inspection issued by an electrical inspection agency approved by the State Board of Electrical Examiners and recognized by the State Fire Marshal shall be filed every three (3) years with the Office of the State Fire Marshal for the following occupancies:
- 2.1.1 Health-Care, and;
- 2.1.2 Day-Care, and;
- 2.1.3 Correction and Detention, and;
- 2.1.4 Education, including their classroom buildings, administration buildings, gymnasiums, auditoriums, and dormitories, and;
- 2.1.5 Bed and Breakfasts, Country Inns, Guest Houses, and;
- 2.1.6 Lodging, Rooming and Boarding Houses, and;
- 2.1.7 Hotels, Motels, and Dormitories.
- 2.2 Assembly occupancies shall file every five (5) years with the Office of the State Fire Marshal a letter of approval of electrical inspection issued by an electrical inspection agency approved by the State Board of Electrical Examiners and recognized by the State Fire Marshal.

3.0 Amusement Rides.

- 3.1 Amusement rides shall have an electrical inspection each time that ride is set up for operation.

- 3.2 A letter of approval of electrical inspection issued by an electrical inspection agency approved by the State Board of Electrical Examiners and recognized by the State Fire Marshal shall be filed with the Office of the State Fire Marshal.

4.0 Other Electrical Inspections.

An electrical inspection on any property may be ordered by written violation notice when deemed necessary by the State Fire Marshal. Such electrical inspection shall be performed by an electrical inspection agency approved by the Board of Electrical Examiners and recognized by the State Fire Marshal and a report shall be filed with the Office of the State Fire Marshal.

5.0 Electrical Consumer Products.

Symbol Of Testing Laboratory Required. A person may not sell or distribute an electrical consumer product which is intended ultimately for the personal use of a consumer in or around a permanent or temporary household or residence, unless the product is clearly labeled, marked, or stamped with the symbol of an electrical testing laboratory which is certified by the State Fire Marshal to test products to determine that they are safe for use.

Chapter 3 Exit Plans

1.0 Theater Exit Plans.

- 1.1 A plan showing the capacity and location of exit ways and aisles leading thereto shall be submitted for approval to the State Fire Marshal and an approved copy shall be displayed on the premises of all indoor theaters.
- 1.2 Every indoor motion picture theater shall furnish and have flashed on the screen prior to each show the above exit plan.

2.0 Motel and Hotel Exit Plans.

- ~~2.1~~ There shall be conspicuously posted in motels and hotels, in each sleeping room, a plan of all exits and fire escapes, detailing the path of egress from said room and the location of each fire alarm station along that path.

Chapter 4 Manufactured Home Installations, Sites, and Communities

1.0 Manufactured Home Installations, Sites, And Communities.

In addition to the requirements of the Standard for Fire Safety Criteria for Manufactured Home Installations, Sites, and Communities, NFPA 501A, as adopted and/or modified by these Regulations, every manufactured home installation, site, and/or community owner or operator shall furnish to the Emergency Dispatch Center having jurisdiction a plot plan of the installation, site, and/or community showing the manufactured home installation. The owner or operator shall also assign numbers to all manufactured homes in a consecutive order and place or have placed the assigned number in a readily visible location on each manufactured home, to eliminate any confusion in the event emergency service, fire, police, or ambulance is needed.

Chapter 5 Access for Emergency Personnel and Apparatus

1.0 General.

- 1.1 Scope.
- 1.1.1 This chapter shall apply to all buildings and /or facilities which may require the response of emergency personnel.
- 1.2 Purpose.
- 1.2.1 The purpose of this chapter is to ensure access to buildings and other facilities for the purpose of providing emergency services. Access for emergency vehicles shall be provided by means of streets, roads, alleys, access roadways, and/or dedicated fire lanes.
- 1.3 Application.
- 1.3.1 This chapter shall apply to all new buildings, structures, or additions as specified in Regulation 701.
- 1.3.2 In the case of an existing building undergoing an occupancy change, the existing building shall comply with these Regulations and shall be reviewed under the provisions of Section 9.0.
- 1.4 Definitions.

- 1.4.1 For specific definitions, see Regulation 701, Chapter 2. The definitions as found in this section shall be in addition to the definitions found in other sections of these Regulations and shall be applicable to this chapter.

Access Roadway – A private non-dedicated roadway that connects a public street with a fire lane.

Bifurcated Access Roadway – An access roadway or street constructed with an entrance lane and exit lane separated by a planting, island, or other physical barrier.

Building Access – Access to a building's exterior entrances, exits and other safety equipment (i.e. fire department connections, fire hydrants, etc) that will allow emergency services to access the building or equipment within a reasonable distance from parked emergency vehicles.

Fire Lane – A street that provides access to a building for Emergency Services Apparatus at all times.

Edge of Street – Shall be base of curb, the outer edge of pavement, or the outer edge of the designated fire lane.

Emergency Services – Shall include all fire and emergency services as regulated by the State Fire Prevention Commission.

Emergency Services Access – That portion of accessibility to any property which is necessary for emergency vehicles to gain access to fire protection equipment during an emergency condition.

Fire Lane Access – That portion of the building perimeter that is required to have fire lanes.

Perimeter Access – That portion of the building perimeter that is accessible by emergency services personnel and is within ~~400~~ 200 feet of a street and capable of supporting fire ground operations.

NOTE: The phrase "fire ground operations" is intended to include providing emergency personnel access to utilize ground ladders, hose operations, and like tasks but not necessarily positioning of fire apparatus.

Perimeter, Building – The measurement of the building's exterior walls along the largest horizontal projection of the roof or floor above.

Primary Entrance – The principle entrance or exit door to a building for use by emergency services.

Road – See Street

Street – A thoroughfare (street, avenue, road, fire lane or boulevard, etc.) which has been devoted for vehicular use by the public and shall be permitted to be utilized for access by Emergency Services Apparatus. For the purpose of this Regulation, a street shall be a minimum of 14 feet in unobstructed clear width one or two way traffic.

Yellow Color – The specific color yellow shall be the uniformly accepted yellow as utilized by State of Delaware Department of Transportation (DelDOT). Only vivid and durable paint shall be used and shall be suitable for street surfaces.

2.0 Emergency Access

- 2.1 All premises where emergency personnel may be called upon to provide emergency services, which are not readily accessible from streets, shall be provided with suitable gates, access roads, and fire lanes so that all buildings on the premises are accessible to emergency apparatus.

NOTE: This section is based upon both a Truck Company turning radius and an Engine Company turning radius. The designer may use computer-based software to illustrate these radii or use specific data obtained from the fire department having jurisdiction to graphically illustrate this.

- 2.2 In the case of one- and two-family dwellings emergency service access shall be provided in such a manner so that emergency apparatus will be able to locate within 100 feet from the street to the primary entrance.

- 2.2.1 Where alleys are provided, pumpers shall be able to access all portions of the alley without strict restrictions for entrance radii.

NOTE: A pumper is a fire department apparatus defined by the National Fire Protection Association and carrying up to a maximum of 1000 gallons of water.

- 2.3 Any dead end road more than 300 feet in length shall be provided with a turn-around or cul-de-sac arranged such that emergency apparatus will be able to turn around by making not more than one backing maneuver. The turn-around or cul-de-sac shall be arranged as follows:

- 2.3.1 Turn-around - Turn-arounds shall be arranged in accordance with one of the four standard designs shown in Figure 5-2, Figure 5-3, Figure 5-4 and Figure 5-5
- 2.3.2 Cul-de-sac - The minimum paved radius of a cul-de-sac is 38 feet unobstructed as shown in Figure 5-1.

Figure 5-1

CUL-DE-SAC




Figure 5-2.

Shaded Area = 182 square yards





Figure 5-3.

Shaded Area = 158 square yards







Figure 5-5.
Shaded Area = 136 square yards



- 2.4 A lock box containing any and all means necessary for fire department access shall be provided at the following occupancies:
 - 2.4.1 Any occupancy that contains a fire alarm signaling system that is monitored off-site, or
 - 2.4.2 Any occupancy that contains an automatic sprinkler system.

Exception No. 1: Where an occupancy has on-site 24 hour guard service or is operating on a manned 24 hour operational cycle.

Exception No. 2: Where the fire department, in whose district the occupancy is located, indicates in writing to the State Fire Marshal that the lock box is not necessary.

Exception No. 3: One- and Two-Family dwellings.

NOTE: "Any and all means necessary" may include keys, keypad access, tools or other devices.

- 2.5 The lock box, as specified in 2.4, shall be listed or approved by the State Fire Marshal for the intended use and installed in such a manner that the fire department will have access to the box.
 - 2.5.1 The lock box shall contain any or all means needed for entry into the building or property.
 - 2.5.2 Lock box contents shall be updated when tenants change, ownership changes, or any time locks are changed or re-keyed.
- 2.6 Gated Communities and Gated Commercial Properties
 - 2.6.1 The requirements of this section shall apply to all new gates installed and for any gate replacing more than 50% of the hardware and software after September 13, 2004.
 - 2.6.2 Fire Department access shall be provided to all otherwise inaccessible gated communities, subdivisions, developments, gated commercial properties or property by any other name through the use of a system or device approved by the Office of the State Fire Marshal after consultation with the local Fire Chief.
 - 2.6.3 The system or device required in 2.6.2 shall be located in an area accessible to the fire department approved by the Office of the State Fire Marshal after consultation with the local Fire Chief.
 - 2.6.3.1 All gates shall be either automatic or manual.
 - 2.6.3.1.1 An automated system shall consist of one manual and one automated means to open the gate. The owner or their representative shall meet with the local Fire Chief prior to submission to the Office of the State Fire Marshal to agree on the system. A letter of agreement shall be created, and signed by both parties. The letter shall include a detailed description of both the manual and automated means.
 - 2.6.3.1.2 A manual gate shall consist of one manual means to open the gate. The owner or their representative shall meet with the local Fire Chief prior to submission to the Office of the State Fire Marshal to agree on the means to open. A letter of agreement shall be created, and signed by both parties. The letter shall include a detailed description of the manual means to open.

NOTE: The owner or representative, such as a Homeowner's Association or a Real Estate Management Company, should invite the gate contractor to the meeting with the Fire Chief so issues can be resolved prior to the plan submission. A representative of the Office of the State Fire Marshal can also be invited to the meeting if deemed necessary by either party.

- 2.6.3.2 To be considered accessible for fire department apparatus the actual clear openings shall be not less than 14 feet, the paved surface through the gate shall be not less than 12 feet, and the gate shall be setback from the perpendicular street by at least 50 feet.

Exception: If the 50 foot setback above is not possible, the actual clear openings and the paved surface through the gate shall be made wider than set forth above in order to accommodate all responding emergency response apparatus.

- 2.6.3.3 Plans submitted to the Office of the State Fire Marshal shall be provided at 1:20, 1:30, 1:40, or 1:50 scale.
- 2.6.4 The owner and/or occupant of the property requiring fire department access as specified in 2.6.2 and 2.6.3 shall maintain the approved system or device in strict accordance with the manufacturer's guidelines.
- 2.6.5 The owner and/or occupant of the property requiring fire department access shall not modify access in any manner that could prevent fire department access without obtaining prior approval from the Office of the State Fire Marshal.

3.0 Emergency Services Access to Buildings

NOTE: This section is for buildings where fire lanes are not required and not regulated under Section 4.0

- 3.1 This section shall apply to buildings that do not require fire lanes but still require emergency services accessibility.

3.1.1 Buildings Requiring Accessibility by Occupancy

- 3.1.1.1 Assembly
- 3.1.1.2 Educational
- 3.1.1.3 Day Care
- 3.1.1.4 Health Care
- 3.1.1.5 Ambulatory Care
- 3.1.1.6 Detention and Correction
- 3.1.1.7 Residential, except one and two family
- 3.1.1.8 Any Mercantile exceeding 1,500 gross square feet
- 3.1.1.9 Any Business exceeding 1,500 gross square feet
- 3.1.1.10 Any Storage exceeding 1,500 gross square feet, or storing any Tier II hazardous materials as defined by the Department of Natural Resources and Environmental Control.
- 3.1.1.11 Any Industrial exceeding 1,500 gross square feet, or storing any Tier II hazardous materials as defined by the Department of Natural Resources and Environmental Control.

3.2 Building Access shall be in accordance with Table 5-1.

Table 5-1
Accessibility Table

Automatic Sprinkler System provided in accordance with NFPA 13	No	Yes
OCCUPANCY¹	Percent of Building Perimeter	Percent of Building Perimeter
Assembly	50	25
Educational ²	50	25
Day Care		
Home ³	0	0
Center	50	25
Health Care	100	50
Ambulatory Health Care	50	25
Detention & Correction	TBDFM	TBDFM
Residential		
Rooming & Lodging	30	15
Hotel/Dorm	70	35
Apartment	70	35
Board & Care	50	25
Mercantile	50	25
Business	30	15
Industrial	50	25
Storage	50	25

TBDFM = To Be Determined in consultation with the Office of the State Fire Marshal.

¹. For Mixed Use occupancies, accessibility shall be based on the floor with the individual occupancy requiring the

greatest accessibility coverage.

2. Educational shall include educational assembly buildings with mixed uses and shall not be considered as mixed use.
3. For Day Care Homes, see 3.4.4.

3.3 The State Fire Marshal may consider other design criteria for existing properties in a traditional urban setting on an individual basis, based upon the nature and degree of hazard associated with the building and/or characteristics of the site.

3.4 Streets and Access Roadways shall be permitted to be utilized to achieve the required Building Access.

3.4.1 Building Access shall be no further than 50 feet from a primary entrance.

3.4.2 Where buildings are provided with an automatic sprinkler system installed in accordance with NFPA 13, access shall be no further than 100 feet from the primary entrance.

Note: See Figure 5-6 – Building Access – With No Fire Lane

3.4.3 Building Access shall be provided by a pervious or impervious surface which is capable of supporting the load of all emergency services apparatus and shall be designed in accordance with accepted engineering practices.

3.4.3.1 Where pervious surfaces are used for perimeter access, the design and location shall be evaluated by the local Fire Chief and approved by the Office of the State Fire Marshal.

3.4.4 In the case of a Day Care homes located in one- and two-family dwellings, emergency service access shall be provided in such a manner so that emergency apparatus can be positioned within 100 feet to the primary entrance.

3.5 Perimeter Access minimum width shall be 15 feet measured from the face of the building at grade with a maximum slope of ten percent (10%). Plantings and utility services (includes condenser units, transformers, etc.) shall be permitted within the perimeter access, and shall not interfere with emergency services fire ground operations.

3.5.1 If a physical barrier (fence, pond, steep slope, etc) prevents access, that portion of the building perimeter shall not be included in the calculation of Percent of Perimeter Access.

3.6 Access to fire protection ~~systems~~ features shall meet the requirements of Chapter 6.

Note: See Figure 5-7 – Perimeter Access – With No Fire Lane

4.0 Emergency Services Access to Buildings That Require Fire Lanes

4.1 This section applies to all buildings:

4.1.1 Exceeding 10,000 gross square feet, or

4.1.2 Three (3) or more stories above grade, or

4.1.3 35 feet or more in height, or

4.1.4 Buildings housing or containing materials or processes classified as High Hazard.

4.2 Fire Lane Access and Perimeter Access shall be in accordance with Table 5-2.

4.2.1 In cases where Regulation 702, Chapter 4, Section 1.1.1, Exception 2 applies, or where no fire suppression system is provided, the following access shall apply:

4.2.1.1 Fire lane access shall be 50%.

4.2.1.2 Perimeter access shall be 100%.

Note: See Figure 5-8 – Fire Lane and Perimeter Access – Without Fire Suppression

4.3 The State Fire Marshal may consider other design criteria for existing properties in a traditional urban setting on an individual basis, based upon the nature and degree of hazard associated with the building and/or characteristics of the site.

4.4 Fire Lanes shall be provided and designed in accordance with Section 6.0 of this chapter and marked in accordance with Section 7.0 of this chapter.

4.5 Perimeter Access minimum width shall be 15 feet measured from the face of the building at grade with a maximum slope of ten percent (10%). Plantings and utility services (includes condenser units, transformers, etc.) shall be permitted within the perimeter access, provided they do not interfere with the emergency services fire ground operations.

4.5.1 If a physical barrier (fence, pond, steep slope, etc) prevents access, that portion of the building perimeter shall not be included in the calculation of Percent of Perimeter Access.

Note: See Figure 5-9 – Fire Lane and Perimeter Access with Fire Suppression

4.5.2 Percent of Perimeter Access requirements shall include the required Percent of Fire Lane Access requirements of Table 5-2.

Accessibility Table
Table 5-2

	Percent of Fire Lanes			Percent of Perimeter Access		
	1-2	3-4	> 4	1-2	3-4	> 4
Height	up to 25'	>25 to 50'	> 50'	up to 25'	>25 to 50'	> 50'
OCCUPANCY¹						
Assembly	50	50	50	N/A	N/A	100
Educational ²	50	75	75	N/A	N/A	100
Day Care Center	25	50	75	50	75	100
Hospital	50	75	75	100	100	100
Nursing Home	25	50	75	75	75	100
Ambulatory Health Care	25	25	50	N/A	50	75
Detention & Correction	TBDFM	TBDFM	TBDFM	TBDFM	TBDFM	TBDFM
Residential	25	35	75	50	75	100
Mercantile	25	50	50	50	75	75
Business	25	25	50	N/A	50	75
Industrial	25	TBDFM	TBDFM	50	TBDFM	TBDFM
Storage	25	TBDFM	TBDFM	50	TBDFM	TBDFM

TBDFM = To Be Determined in consultation with the Office of the State Fire Marshal.

1. For Mixed Use occupancies, accessibility shall be based on the floor with the individual occupancy requiring the greatest accessibility coverage.

2. Educational shall include educational buildings with mixed uses and shall not be considered as mixed use.

NOTE: For the purposes of this Regulation and application of the Accessibility Table, the fire lane portion was based upon a 100 foot Aerial reach and the width of aerial stabilizers. The Perimeter Access portion was based upon standard fire ground operations.

5.0 Design of Access Roadways.

- 5.1 Where emergency services apparatus have to utilize access roadways to reach designated fire lanes, such access roadways shall be constructed to meet the minimum engineering specifications and/or requirements pursuant to the Delaware Department of Transportation or local jurisdictions for paved roadways.
- 5.2 All access roadways shall be paved and be a minimum of 20 feet clear width for two-way traffic and 14 feet clear width for one-way traffic. The paved width of access roadway shall be measured from edge of parking spaces, or face of curb for vertical curb and back of curb for mountable curb, or edge of pavement if there is no curbing.
- 5.3 The design professional of record shall certify that the access roadway was built to the minimum requirements as listed in 5.1.
- 5.4 Access roadways not utilized as fire lanes shall not require marking.

6.0 Design of Fire Lanes.

- 6.1 The following criteria shall be utilized to effect a design submittal for review and approval.

NOTE: Design and location of fire lanes around buildings, structures or properties are dependent on many considerations, such as occupancy, building height, construction, property grades, etc.

- 6.2 Fire lanes shall be a minimum 24 feet in clear width.
- 6.3 Fire lanes shall be required to run along the front of the building as determined by the primary entrance(s). In cases where there is more than one primary entrance(s), each shall be served by a fire lane even if this exceeds the percentage as required by Section 4.0, Table 5-2.
 - 6.3.1 Parking shall be prohibited between the building and the fire lane where 4.2.1 applies.
 - 6.3.2 Parking shall be prohibited in front of the primary entrance for a width of not less than 1.5 times the width of the door(s) or for 10 feet, whichever is greater.
 - 6.3.2.1 Parking shall be prohibited in front of any secondary entrance(s) located within the required perimeter and fire lane access, for a width of not less than the width of the entrance door(s).
 - 6.3.2.2 Where multiple primary entrances are provided, 15 foot wide unobstructed emergency services access shall be provided in parking rows at intervals not to exceed 90 feet.

Note: Examples of multiple primary entrances may include strip shopping centers, town centers, and traditional design neighborhoods.

- 6.3.2.3 Containers placed within parking spaces between the fire lane and the building shall be limited to one container no greater than 12 feet in height.
 - 6.3.3 Where parking is provided between the building and the fire lane, unobstructed emergency services access shall be provided in parking rows at intervals not to exceed 90 feet.
 - 6.3.4 Parking and/or obstructions shall be prohibited in front of fire department connections for a distance measuring from the center line and extending four feet on both sides.
 - 6.3.5 Parking shall be prohibited for 15 feet, in any direction, from an intersection at the corner of a building.
 - 6.3.6 Handicap access shall be permitted to be used as the unobstructed access referred to in 6.3.2.2.
- 6.4 The closest edge of fire lanes shall not be located closer than ten (10) feet to the exterior wall.
 - 6.4.1 Where parking is located between the building and the fire lane, parking shall not be located closer than 15 feet to the exterior wall.
- 6.5 The closest edge of fire lanes shall not be located further than 50 feet from the exterior wall if one or two stories in height; 40 feet if three or four stories in height, or 30 feet if over four stories in height.
- 6.6 Fire lanes shall be constructed to meet the minimum engineering specifications of the Delaware Department of Transportation requirements for paved roadways.
- 6.7 "Speed Bumps" or any other like device used to reduce vehicle speed shall be limited. They shall be installed pursuant to the State of Delaware Department of Transportation specifications.

NOTE: Where possible, wheel cutouts should be provided for emergency services apparatus.

- 6.8 Where overhangs, canopies, balconies, or any other building or site features must project over any fire lane, an unobstructed vertical clearance of not less than 13'-6" above the fire lane shall be provided.
 - 6.8.1 Overhangs, canopies, balconies, or any other building or site features shall not impair access by emergency apparatus.
 - 6.8.2 Overhangs, canopies, balconies, or any other building or site features shall not reduce the width of any fire lane.
 - 6.8.3 Overhangs, canopies, balconies, or any other building or site features shall not interfere with the effective utilization of fire department aerial devices.
 - 6.8.4 The portion of the building perimeter which contains overhangs, canopies, balconies, or any other building features shall not apply towards the fire lane accessibility requirements of Section 4.0, Table 5-1 in this chapter.

7.0 Marking and Identification of Fire Lanes.

7.1 All fire lanes shall be marked as prescribed within the appropriate section of this regulation and as illustrated by the appropriate figures of this regulation.

7.2 Fire lanes shall be marked as follows:

7.2.1 Both the inner and outer edges of the fire lane shall be marked.

7.2.2 Where curbs are present, the top and face of the curb shall be painted yellow.

7.2.3 Where no curbs are present, a four inch (4") solid yellow demarcation line shall mark the edge(s) of the fire lane.

Note: See Figure 5-10 – Marking and Identification of Fire Lane

7.2.4 Where the four inch (4") solid yellow demarcation line of a fire lane intersects an access roadway or parking lot aisle, it may be marked as follows:

7.2.4.1 A four inch (4") solid yellow demarcation line may continue to run across the intersection of the access roadway or parking lot aisle, or

7.2.4.2 A broken (intermittent) four inch (4") yellow demarcation line may continue to run across the intersection of the access roadway or parking lot aisle, or

7.2.4.3 The four inch (4") solid yellow demarcation line may be omitted at the intersection of the access roadway or parking lot aisle, but shall continue for the remainder of the fire lane where it does not intersect an access roadway or parking lot aisle.

Note: See Figure 5-11 – Marking and Identification of Fire Lane – Intersecting an Access Roadway or Aisle

7.3 Fire lane signs shall be located as follows:

Note: See Figure 5-16 – Approved Sign For Marking Fire Lanes

7.3.1 Fire lane signs shall be spaced at 150 foot intervals maximum.

7.3.2 All fire lane signs shall be located no less than six feet (6') and no higher than eight feet (8') above the pavement.

7.3.3 Signs shall be placed at each end of the fire lane.

7.3.4 Signs shall face all oncoming traffic.

7.3.5 Where no parking is provided between the building and the fire lane, signs shall be posted along the inner curb, building line, or edge of the roadway immediately adjacent to the fire lane.

Note: See Figure 5-12 – Marking and Identification of Fire Lane – No Parking Between Building & Fire Lane

7.4 When a method of parking restriction utilizes a curb island extension to meet the requirements of 6.3.2.2, markings shall be as follows:

7.4.1 Fire lane signs shall be installed in accordance with 7.3.

7.4.2 Four inch (4") solid yellow demarcation lines shall be provided in accordance with 7.2.

7.4.3 The curb of the extension shall be marked parallel to the traffic lane around to the curb tangent.

Note: See Figure 5-13 – Access Requirements – Parking Between Building & Fire Lane with Curb and Sidewalk with Multiple Primary Entrances

7.5 When a method of parking restriction uses demarcation lines to meet the requirements of 6.3.2.2, it shall be as follows:

7.5.1 The space shall be marked with diagonal four inch (4") solid yellow lines and the words "NO PARKING".

7.5.1.1 The words "NO PARKING" shall be no less than six feet (6') in height and 12 feet in length.

Note: See Figure 5-14 – Access Requirements – Parking Between Building & Fire Lane with Sidewalk But without Curb with Multiple Primary Entrances

7.6 Where parking is not restricted roadway markings shall utilize the words "FIRE" and "LANE" in lieu of fire lane signs, and shall conform to the following specifications:

7.6.1 The first word "FIRE" shall be closest to a driver approaching such marking,

7.6.2 Each word shall be at least ten feet (10') in height and 20 feet,

7.6.3 The distance between the word "FIRE" and the word "LANE" shall be no greater than 30 feet, and

7.6.4 The distance from the word "LANE" to the beginning of the second set of roadway markings where the word "FIRE" begins shall be no greater than 100 feet.

Note: See Figure 5-15 – Marking and Identification of Fire Lane – Parking Between Building and Fire Lane

7.7 Where permitted by the State Fire Marshal, a combination of fire lane signs and roadway markings shall be acceptable.

8.0 Marking and Identification of Exits Leading to Fire Lanes.

- 8.1 All building exits leading to fire lanes shall be marked as prescribed within the appropriate section of this regulation and as illustrated by the appropriate figures of this regulation.
- 8.2 All exits shall have minimum four inch (4") solid yellow demarcation lines define specific areas.
 - 8.2.1 ADA blue markings shall be acceptable to meet 8.2 provided they are adjacent to the ADA parking space and used as part of the ADA access.
- 8.3 Demarcation lines on primary exits shall extend no less than 1.5 times the width of the door to the fire lane.
- 8.4 Demarcation lines on secondary exits shall extend no less than the width of the door to the fire lane.
- 8.5 Demarcation lines need not be located on sidewalk surfaces or other surfaces not subject to vehicular traffic, but shall extend from the end of the sidewalk surface or curb line to the fire lane.
 - 8.5.1 Where necessary to extend from the sidewalk to the fire lane the area shall be hatched using four inch solid yellow lines.
- 8.6 No objects, stands, displays, or other impediments shall be located within the demarcation area.
- 8.7 When required by the State Fire Marshal, minimum four inch (4") diameter steel bollards filled with concrete and marked yellow shall be installed at the outermost corners of the exit's demarcation area. The minimum height of the bollard shall be 36 inches above the finished grade of the adjacent surface.

9.0 Existing Buildings and Existing Fire Lane Markings

- 9.1 Existing Buildings
 - 9.1.1 In the case of a building constructed prior to the adoption of this Regulation, this Regulation is not intended to require the degree of access as required for new buildings, but this Regulation does require that access be provided and marked for existing buildings, ON A CASE BY CASE BASIS, as determined by the State Fire Marshal with due consideration to the existing conditions
 - 9.1.2 "Existing" in the context of this section means that the building was already constructed prior to a fire lane regulation being promulgated, prior to the date of these Regulations. The State Fire Marshal shall determine the minimum access and marking required based on the building occupancy, size, and height with due consideration to the existing conditions.
- 9.2 Existing Fire Lane Markings
 - 9.2.1 Requested changes to the existing fire lane markings shall meet all the provisions of this chapter.

10.0 Enforcement

- 10.1 It shall be unlawful for any person to park motor vehicles in, or otherwise obstruct any fire lane.
- 10.2 Enforcement action to require the appropriate design and marking of fire lanes, etc. as required in this Regulation shall be as prescribed in 16 **Del.C.** §6614.
- 10.3 Enforcement action regarding stopping, standing or parking a vehicle in a fire lane shall be as prescribed in 21 **Del.C.** §4179 and/or 21 **Del.C.** §7001.
- 10.4 Enforcement action regarding stopping, standing or parking a vehicle within 15 feet of a fire hydrant shall be as prescribed in this regulation and 21 **Del.C.** §7001 and/or 21 **Del.C.** §4179.
- 10.5 It shall be unlawful for any person to park motor vehicles in or otherwise obstruct a turn-around or a cul-de-sac.

1 DE Reg. 197 (08/01/97)
3 DE Reg. 97 (07/01/99)
6 DE Reg. 1638 (06/01/09)
8 DE Reg. 416 (09/01/04)
10 DE Reg. 342 (08/01/06)
13 DE Reg. 629 (11/01/09)
16 DE Reg. 620 (12/01/12)

Chapter 6 Marking and Identification of Fire Protection Features

1.0 Marking and Identification of Exits

- 1.1 All exits shall be marked as prescribed within the appropriate section of this regulation and as illustrated by the appropriate figures of this regulation.
- 1.2 All exits shall have minimum of four inch (4") solid yellow demarcation lines to define specific areas.
 - 1.2.1 ADA blue markings shall be acceptable to meet 1.2.
- 1.3 Demarcation lines shall extend no less than the width of the door to the edge of street or traffic lane.

1.3.1 Primary entrance doors shall be demarcated no less than 1.5 times the width of the door but no more than 10 feet.

1.3.2 Secondary egress doors shall be demarcated no less than the width of the door.

1.4 Demarcation lines need not be located on sidewalk surfaces or other pedestrian surfaces not subject to vehicular traffic, but shall extend from the end of the sidewalk surface to the edge of street or traffic lane.

1.4.1 Where necessary to extend from the sidewalk to the edge of street or traffic lane the area shall be marked using diagonal four inch solid yellow lines.

1.5 No objects, stands, displays, or other impediments shall be located within the demarcation area.

1.6 When required by the State Fire Marshal, minimum four inch (4") diameter steel bollards filled with concrete and marked yellow shall be installed at the outermost corners of the exit's demarcation area. The minimum height of the bollard shall be 36 inches above the finished grade of the adjacent surface.

Note: See Figure 6-1 - Marking and Identification of Exits without Fire Lanes

16 DE Reg. 620 (12/01/12)

2.0 Marking and Identification of Fire Hydrant Location.

2.1 All fire hydrants shall be marked as prescribed within the appropriate section of this regulation and as illustrated by the appropriate figures of this regulation.

2.2 All fire hydrants shall have minimum of four inch (4") solid yellow demarcation lines to define specific areas.

2.3 Where fire hydrants are located along a curb line with permitted parking, the area between the fire hydrant and the street or fire lane shall be stenciled with four inch (4") demarcation lines and the words "NO PARKING".

2.3.1 The words "NO PARKING" shall be no less than six feet (6') in height and 20 feet in length.

2.3.2 Diagonal demarcation lines on the street shall extend from edge of street to the edge of the traffic lane.

2.3.3 Where a curb is used, the top and face of the curb shall be painted yellow.

2.3.4 Demarcation lines shall be measured from the center line of the fire hydrant and extend for a distance 15 feet on both sides.

Note: See Figure 6-2 - Marking of Fire Hydrants Along Curb

2.4 Where fire hydrants are located on a curb island extension in such a manner that the hydrant is directly accessible to the street or fire lane, the top and face of curb shall be painted yellow.

2.4.1 The curb shall be marked parallel to the traffic lane around to the curb tangent.

2.5 Where fire hydrants are located in parking lots or other areas susceptible to blockage by parked vehicles they shall be treated as follows:

2.5.1 Fire hydrants shall be protected in all directions for a distance of seven feet (7') with barriers or curbing.

2.5.2 An access roadway shall run through the parking area and adjacent to the demarcation area of the fire hydrant.

2.5.3 The access roadway shall extend "from" and "to" a traffic lane.

2.5.4 Minimum four inch (4") diameter steel bollards filled with concrete and marked yellow shall be installed at the outermost corners of the fire hydrant demarcation area. The minimum height of the bollard shall be 36 inches above the finished grade of the adjacent surface.

Note: See Figure 6-3 - Marking of Fire Hydrant in Parking Lot

2.6 The distance between a fire hydrant and the nearest edge of the street shall not be greater than ten feet (10') unless an alternate distance is approved by the State Fire Marshal.

2.7 The steamer connection of all fire hydrants shall be positioned so as to be facing the edge of the street, or traffic lane.

16 DE Reg. 620 (12/01/12)

3.0 Marking and Identification of Sprinkler Connections and Standpipes.

3.1 All standpipe and sprinkler connections shall be marked as prescribed within the appropriate section of this regulation and as illustrated by the appropriate figures of this regulation.

3.2 All standpipe and sprinkler connections shall have minimum of four inch (4") solid yellow demarcation lines to define specific areas.

3.3 Solid yellow demarcation lines shall be measured from the center line of the connection and extend for a distance of four feet (4') on both sides.

3.4 Where parking is allow between the building and the street or fire lane the solid yellow demarcation lines shall extend from the end of the sidewalk surface to the street or fire lane.


- 3.4.1 Markings shall not be required on the sidewalk surface.
- 3.4.2 Where necessary, diagonal four inch (4") solid yellow demarcation lines including the words "NO PARKING" shall be painted to define the specific area.
- 3.5 No objects, stands, displays, or other impediments shall be located within the demarcation area.
- 3.6 When required by the State Fire Marshal, minimum four inch (4") diameter steel bollards filled with concrete and marked yellow shall be installed at the outermost corners of the demarcation area for the fire department connections. The minimum height of the bollard shall be 36 inches above the finished grade of the adjacent surface.
- 3.7 All fire department connections (standpipe and sprinkler) shall have a minimum 12" x 18" sign that reads:
FIRE DEPT. CONNECTION


Sign lettering shall be a minimum of 3 inches (3") in height with red scotchlite letters on white scotchlite background. The sign shall be clearly visible from the fire lane or roadway.

- 3.7.1 Signs using NFPA international symbols shall be an acceptable alternative.

13 DE Reg. 629 (11/01/09)

16 DE Reg. 620 (12/01/12)





PERIMETER ACCESS - WITH NO FIRE LANE


DELAWARE STATE FIRE PREVENTION REGULATIONS



SCALE: N.S.T.
DATE: 5/10
DRAWN BY: S.L.G.

FIG. 5.7

F:\AutoCAD\Projects\2010\DSFM\DSFM-Regulations.dwg, Jul 01, 2010 - 1:56pm



FIRE LANE AND PERIMETER ACCESS - WITH NO SPRINKLERS


DELAWARE STATE FIRE PREVENTION REGULATIONS



SCALE: N.S.T.
DATE: 5/10
DRAWN BY: S.L.G.

FIG. 5.8

F:\AutoCAD\Projects\2010\DSFM\DSFM-Regulations.dwg, Jul 01, 2010 - 1:57pm



FIRE LANE AND PERIMETER ACCESS WITH FIRE SUPPRESSION SYSTEM


DELAWARE STATE FIRE PREVENTION REGULATIONS



SCALE: N.S.T.
DATE: 5/10
DRAWN BY: S.L.G.

FIG. 5.9

F:\AutoCAD\Projects\2010\DSFM\DSFM-Regulations.dwg, Jul 01, 2010 - 1:57pm



CASE 1 - CURB

CASE 2 - WITHOUT CURB

CASE 3 - PARKING

MARKING AND IDENTIFICATION OF FIRE LANE



DELAWARE STATE FIRE PREVENTION REGULATIONS





SCALE: N.S.T.
DATE: 5/10
DRAWN BY: S.L.G.

FIG. 5.10

F:\AutoCAD\Projects\2010\DSFM\DSFM-Regulations.dwg, Jul 01, 2010 - 2:00pm











Figure 5-16
Approved Sign For Marking Fire Lanes





MARKING AND IDENTIFICATION OF EXITS WITHOUT FIRE LANES


DELAWARE STATE FIRE PREVENTION REGULATIONS



SCALE: N.S.T.
DATE: 5/10
DRAWN BY: S.L.G.

FIG. 6.1

F:\AutoCAD\Projects\2010\DSFM\DSFM-Regulations.dwg, Jul 01, 2010 - 2:02pm



MARKING OF FIRE HYDRANTS ALONG CURB


DELAWARE STATE FIRE PREVENTION REGULATIONS



SCALE: N.S.T.
DATE: 5/10
DRAWN BY: S.L.G.

FIG. 6.2

F:\AutoCAD\Projects\2010\DSFM\DSFM-Regulations.dwg, Jul 01, 2010 - 2:04pm



16 DE Reg. 620 (12/01/12)
19 DE Reg. 843 (03/01/16) (Final)